

CHATHAM COUNTY PURCHASING & CONTRACTING DEPARTMENT

ADDENDUM NO. 1 TO 17-0043-4

**FOR: LAROCHE AVENUE AT DERENNE AVENUE INTERSECTION
IMPROVEMENTS**

**PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR
CHANGES:**

RESPONSE TO QUESTION RECEIVED:


1. Q) Will the pushbutton stations on this project require custom messaging that call out the street names for the blind/disabled, also referred to as accessible type?
A) Yes.

**NOTE: REPLACE CURRENT BID SHEETS (3 pages) WITH THE ATTACHED
REVISED BID SHEETS (3 pages)**

BID OPENING REMAINS: 2PM, TUESDAY, JUNE 13, 2017

**THE PROPOSER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES
AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.**

5/25/17
DATE


ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY

BID SHEET FOR : LAROCHE AVENUE AT DERENNE AVENUE

3003044

ITEM NO. DESCRIPTION UNITS QTY. UNIT COST TOTAL

ROADWAY

150-1000	TRAFFIC CONTROL - LAROCHE AT DERENNE INTERSECTION IMPROVEMENT	LS	1		
210-0100	GRADING COMPLETE - LAROCHE AT DERENNE INTERSECTION IMPROVEMENT	LS	1		
318-3000	AGGR SURF CRS	TN	20		
402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIM	TN	223		
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	301		
413-0750	TACK COAT	GL	273		
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	2732		
441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	68		
441-0104	CONC SIDEWALK, 4 IN	SY	91		
441-0303	CONC SPILLWAY, TP 3	EA	1		
441-0304	CONC SPILLWAY, TP 4	EA	1		
441-0740	CONCRETE MEDIAN, 4 IN	SY	27		
441-4020	CONC VALLEY GUTTER, 6 IN	SY	14		
441-5002	CONCRETE HEADER CURB, 6 IN, TP 2	LF	36		
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	446		
611-8050	ADJUST MANHOLE TO GRADE	EA	7		
634-1200	RIGHT OF WAY MARKERS	EA	12		
643-8200	BARRIER FENCE (ORANGE), 4 FT	LF	200		
665-0250	ADJUST WATER/GAS VALVE COVER TO GRADE	EA	4		
668-2100	DROP INLET, GP 1	EA	1		

**BID SHEET FOR : LAROCHE AVENUE AT DERENNE AVENUE
3003044**

ITEM NO.	DESCRIPTION	UNITS	QTY.	UNIT COST	TOTAL
SIGNING & MARKING					
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	3		
636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	SF	4		
636-2070	GALV STEEL POSTS, TP 7	LF	27		
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	6		
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	963		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	89		
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	793		
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	123		
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	16		
SIGNALIZATION					
636-1041	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 9	SF	126		
639-3004	STEEL STRAIN POLE, TP IV, INCL COMB 45FT/50FT MAST ARMS	EA	1		
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 1	LS	1		
682-6233	CONDUIT, NONMETL, TP 3, 2 IN	LF	800		
682-9950	DIRECTIONAL BORE - 3 IN	LF	85		
682-9950	DIRECTIONAL BORE - 6 IN	LF	160		
687-1000	TRAFFIC SIGNAL TIMING -1	LS	1		
PERMANENT EROSION CONTROL					
706-1003	TURF ESTABLISHMENT, TP C	AC	1		

**BID SHEET FOR : LAROCHE AVENUE AT DERENNE AVENUE
3003044**

ITEM NO.	ITEM DESCRIPTION	UNITS	QTY.	UNIT COST	TOTAL
TEMPORARY EROSION CONTROL					
163-0232	TEMPORARY GRASSING	AC	1		
163-0240	MULCH	TN	10		
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	1		
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	516		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	1		
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	1032		
999-9999	FIELD CONDITION ALLOWANCE	LS	1		\$10,000

TOTAL BID	
------------------	--

NAME / TITLE

COMPANY

ADDRESS

PHONE / FAX NO'S.

E-MAIL