

CHATHAM COUNTY PURCHASING & CONTRACTING DEPARTMENT

ADDENDUM NO. 2 TO 20-0079-4

FOR: HENDERSON GOLF CLUB 18TH FAIRWAY STABILIZATION

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

1. SEE THE ATTACHED SHEET FOR QUESTIONS RECEIVED (1 page)

BID OPENING REMAINS:

2:00 PM, WEDNESDAY, OCTOBER 28, 2020

THE PROPOSER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

10/22/20
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY

Additional Questions Received:

1. Q) When can we conduct a site visit ?
A) ***Anytime – Let the golf course you are there and be careful of golf balls.***
2. Q) What is the size of the two inflow pipes?
A) ***Not certain. Best guess would be no smaller than 24" and no larger than 36".***
3. Q) Are they continuous flow?
A) ***All of the ponds outfall through the pond where you will be working. The ponds are not continually flowing. Only during storm events and shortly after.***
4. Q) If there is a control structure would it prevent or allow us to or not to pipe plug each?
A) ***You can plug the pipes and pump down the one pond. However, when a significant rain event occurs, the pipes will need to be open to allow the water to flow through. Once the event is over, the pipes can be plugged again and pumping resumed.***
5. Q) What is the size of the outflow pipe?
A) ***The outflow for this pond is a ditch which flows into the woods and connects to a canal. There is no structure or pipe.***
6. Q) Where is a suitable discharge area for the pump?
A) ***The outfall ditch into the woods.***
7. Q) What is the distance to the discharge area?
A) ***Adjacent to the pond.***
8. Q) Other than concrete and grass line items, who is responsible for other damages incurred during the project?
A) ***The County will review each event when damage occurs during construction. If the damages are due to negligence of the contractor, the contractor shall be responsible. If the damages are unavoidable and unforeseen, the County will be responsible.***
9. Q) Where is the approved laydown area for materials?
A) ***The laydown area will be at the golf course shop located just west of the customer parking area.***
10. Q) Does this project allow a pump to run overnight?
A) ***Yes with a generator. The contractor would be responsible for the operation of the pump and generator.***
11. Q) Will there be restricted work days or hours for course play?
A) ***No time restrictions have been set for working or for course play.***